

ELEMENTOS CABLEADO ESTRUCTURADO BLOCK 1	
DESCRIPCION	CANTIDAD
PLANTA BAJA (MDF)	
RACK COMUNICACIONES 40U	1
PATCH PANEL F.O.	1
MODULO LC DUPLEX	5
ORDENADOR CABLE 1U	1
ORDENADOR CABLE 2U	1
PATCH PANEL UTP CAT.6 (24 puestos)	2
PATCH CORD F.O. LC-LC MM (62,5/125um) x 1m	5
PATCH CORD UTP CAT.6 x 0,6m	40
FIBRA OPTICA MM (62,5/125um)	220+7+12+17+22 (278m)
CABLE UTP CAT.6	40x50 (2000mts)
ROSETA RJ45	40
JACK RJ45	40
PATCH CORD UTP CAT.6 x 2m	40
PISOS 1,2,3 y 4 (IDF's)	
RACK MURAL 8U	4x1 (4)
PATCH PANEL F.O.	4x1 (4)
MODULO LC DUPLEX	4x1 (4)
ORDENADOR CABLE 1U	4x1 (4)
ORDENADOR CABLE 2U	4x1 (4)
PATCH PANEL UTP CAT.6 (24 puestos)	4x2 (8)
PATCH CORD F.O. LC-LC MM (62,5/125um) x 1m	4x1 (4)
PATCH CORD UTP CAT.6 x 0,6m	4x40 (160)
CABLE UTP CAT.6	4x40x50 (8000mts)
ROSETA RJ45	4x40 (160)
JACK RJ45	4x40 (160)
PATCH CORD UTP CAT.6 x 2m	4x40 (160)

ELEMENTOS CABLEADO ESTRUCTURADO BLOCK 3	
DESCRIPCION	CANTIDAD
PLANTA BAJA (MDF)	
RACK MURAL 8U	1
PATCH PANEL F.O.	1
MODULO LC DUPLEX	5
ORDENADOR CABLE 1U	1
ORDENADOR CABLE 2U	1
PATCH PANEL UTP CAT.6 (24 puestos)	2
PATCH CORD F.O. LC-LC MM (62,5/125um) x 1m	5
PATCH CORD UTP CAT.6 x 0,6m	40
FIBRA OPTICA MM (62,5/125um)	7+12+17+22 (58m)
CABLE UTP CAT.6	40x50 (2000mts)
ROSETA RJ45	40
JACK RJ45	40
PATCH CORD UTP CAT.6 x 2m	40
PISOS 1,2,3 y 4 (IDF's)	
RACK MURAL 8U	4x1 (4)
PATCH PANEL F.O.	4x1 (4)
MODULO LC DUPLEX	4x1 (4)
ORDENADOR CABLE 1U	4x1 (4)
ORDENADOR CABLE 2U	4x1 (4)
PATCH PANEL UTP CAT.6 (24 puestos)	4x2 (8)
PATCH CORD F.O. LC-LC MM (62,5/125um) x 1m	4x1 (4)
PATCH CORD UTP CAT.6 x 0,6m	4x40 (160)
CABLE UTP CAT.6	4x40x50 (8000mts)
ROSETA RJ45	4x40 (160)
JACK RJ45	4x40 (160)
PATCH CORD UTP CAT.6 x 2m	4x40 (160)